

Certificate No. NESA-T137

Version No. 1.1

Approval date 24 May 2022

Approved by Acting General Manager Technical Standards

This certificate is issued to

Supplier Integrated Recycling

In respect of

Manufacturer Integrated Recycling

Product description Duratrack composite sleeper

Item identification

Application Main line standard-gauge track between signal TOT2 (8.342KP) to 3U pts (9.800KP) at Tottenham, Victoria

Relevant Standards

Conditions of Approval

ARTC:

1. 25 Duratrack composite sleepers to be installed as a 1 in 6 arrangement with timber sleepers (i.e. 5 composite and 1 timber).
2. Installation and maintenance to be as per manufacturer's instruction.
3. Trial location to be included on TSMP special location register when trial commences.
4. Sleeper performance to be monitored as per Index 26 Proposed ARTC Test Timeline and Item List V3.
5. Defected sleepers shall be replaced with new Duratrack sleepers or timber sleepers.
6. Duratrack sleepers shall be removed at the completion of this trial.

Note/Comments

Issue date 24/05/2022

Expiry date
N/A

Issued by

Acting General Manager Technical Standards